

RIC 2013 PWROG Program to Address NRC GSI-191

Jeff Brown Arizona Public Service March 12, 2013

The PWR Owners Group



PWROG In-vessel Fiber Program Overview

- · Program Objective
- · Organization and Program Development
- Technical Program
- · Plant Data and Assumptions
- · Program Status
- · Expectations
- Schedule

2



Program Objective

- Establish defensible acceptance criteria to ensure long term core cooling
 - PWROG GSI-191 deterministic in-vessel fiber program supports resolution of the in-vessel issues for Option 2 plants
 - Program results will provide higher limits than WCAP 16793, R2
 - Limits applicable to groups of plants as opposed to a single bounding limit
 - Higher limits will minimize insulation modifications and will provide margins for future operability issues

3





Technical Program (continued)


- Integrated water / chemistry tests and scaled head loss testing
 - Plant survey data identified that plants are much more diverse, leading to smaller bins and more groups of plants to consider
 - Program refinements
 - Expansion of autoclave testing to identify problematic sump fluid chemistry
 - · Incorporation of high temperature scaled head loss testing
 - · Parallel expansion of flow loop to permit concurrent testing
 - Head loss validation testing in full scale FA test loop

7

The PWR Owners Group



Technical Program (continued)



8

The PWR Owners Group



Technical Program (continued)

- · Thermal-hydraulic analyses
 - LOCA analysis objective is to determine effects of core inlet blockage on the ECCS core cooling function and to inform FA testing program
 - Analyses to be completed representing appropriately grouped system designs
 - Model includes alternate core bypass flow paths and / or steam generator spillover (hot-leg breaks)
 - Analyses predicated on conservative assumptions and initial conditions

9



Program Status

- · Fiber characterization testing
 - Testing on-going
 - First test matrix results are being evaluated
- · Integrated water/chemistry and head loss program
 - Autoclave tests in process
 - Initial autoclave test results under review
 - High temperature flow loop design review in progress

10

The PWR Owners Group



Program Status (continued)

- · Thermal-hydraulic analyses
 - B&W plant design Alternate flow paths are a viable option if core inlet is blocked
 - W plant designs w/ up-flow baffles Analysis results are promising that most plants will be able to demonstrate alternate flow paths are viable as well
 - W plants w/ down-flow baffles Analyses in progress
 - CE plants may be more challenging
 - W (COBRA-TRAC) and AREVA (RELAP) methods are showing similar results

11

The PWR Owners Group



Expectations

- Thermal hydraulic analyses indicate that significantly lower core flows needed for core cooling
- In-situ corrosion product formation expected to demonstrate prototypical materials
- Test program will produce defensible results based on appropriate technical development
- All plant groups are expected to realize increased allowable in-vessel fiber load

12





Schedule

Milestone	Start	Completion
NRC Status	March, 2013	
PIRT	On-going	March, 2013
Fiber Characterization	On-going	April, 2013
Thermal-hydraulics	On-going	July, 2013
Autoclave Testing	On-going	June, 2013
Integrated Testing	June, 2013	January, 2014
Confirmatory Testing	January, 2014	February, 2014
Boric Acid Precipitation (Design)	On-going	April, 2013